ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 1st April 1935.

The attention of the public is invited to the notification calling for tenders for constructing a building for locating Arrack and Toddy shops near Binny Mills, Bangalore City, published on pages 768-769 of Part VI of the *Mysore Gazette*, dated 4th April 1935.

The last date of receiving tenders is 27th April 1935.

Abstract Notification dated 1st April 1935.

The attention of the public is invited to the notification calling for tenders for constructing a building for the Boy Scouts' Headquarters Office, Bangalore, published on pages 769-770 of Part VI of the *Mysore Gazette*, dated 4th April 1935.

The last date of receiving tenders is 27th April 1935.

Notification dated 8th April 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 29th April 1935 (2 P.M.) for constructing a Building for the Testing Laboratory in the Government Porcelain Factory at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed:—

4. Each tender must be accompanied by a deposit of rupees three hundred and fifty only (Rs. 350) in cash or Government Promissory Notes, as earnest money, and be suprescribed "Tender for Constructing a Building for the Testing Laboratory in the Government Porcelain Factory, Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Transfer of work to the third parties by selected contractors will not be countenanced by the Department and in the case of any such attempt, the earnest money is liable to be forfeited at the discretion of the Superintending Engineer, Mysore Circle.

Abstract estimate of quantities for Constructing a Testing Laboratory at Porcelain Factory Building, Bangalore.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
1	Earth work excavating foundation and stacking at place to be shown and filling in basement with watering and tamping	C.yd.		98	
2	Granite jelly concrete in lime mortar (1 : 2 : 4)	C.ft.		772	
3	Granite size stone in mortar with bond stones of full thickness of wall at every 6′ apart in every course	,,		1,881	
4	Burnt brick in clay superstructure	,,		587	
4(*a*)	Burnt brick in clay from 13½′ to top	,,		1,417	
5	Burnt brick in mortar	,,		2,498	
5(*a*)	Burnt brick in mortar above 13½′ height ..	,,		504	
6	Burnt brick in mortar arch work	,,		133	
7	Burnt stone slabs 6″ thick, exposed surfaces two line dressed and other surfaces roughly dressed and fixed	S.ft.		926	
7(*a*)	Burnt stone slabs 6″ thick roughly dressed and fixed in higher portions	,,		281	
8	Teak wood doors, frame 4″×5″, panelled shutters 1¼″ thick, with iron fittings, including fixing in position etc., complete	,,		32	
9	Teak wood door, frame 4″×6″, panelled shutters fourfold, 1½″ thick, with parliamentary hinges, etc., complete including fixing to the position	,,		64	
10	Teak wood windows, frame 4″×5″ with glazed shutters 1¼″ thick inside with iron bars, fittings, etc., complete including fixing in position	,,		327	
11	R. C. Ornamental perforated ventilators 2″ thick including fixing	,,		125	
12	Tata's Tested Rolled Steel girders including painting and fixing	Cwt.		15·5	
12 (*a*)	Circular pillars 1⅛′ dia. with base and capitals (with 9″ dia. stone core finished with fine mortar)	Each		2	
13	Teak wood wrought and put up including wood oiling	C.ft.		157·25	
14	Pukka terrace 9″ thick, 2 courses of terrace bricks and brick concrete and two courses of flat tiles, including plastering at top and bottom and white washing complete	Sqr.		6·54	
15	Cornice 9″ thick	R.ft.		184	
16	Parapet wall brick in mortar base 1⅛′×1½′, wall ¾′×1½′ with top cornice and lime mortar plastering and white washing ..	,,		80	
17	Rain water down pipes 3″ dia. 6′ long of zinc sheet including fixing	No.		6	
18	Lime mortar plastering with fine finish ..	Sqr.		72·39	
19	Cement pointing	,,		3·46	
20	Steel trusses 25′×4½″ clear span (special design to bear extra loads up to 250 lbs. for testing Insulators) including Lewis bolts 2′×1″ dia. with bottom plate ¾″ thick 1′ sq. including drilling holes in bed slabs, painting, hoisting and fixing, etc., complete	Cwt.		2	
21	Mangalore Tiled roofing first class, on teak reepers including wood oiling to reepers, etc., complete	Sqr.		15·91	
22	Supplying and fixing ridge tiles including cement pointing	R.ft.		43	

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
23(*a*)	Mortar bands (9″×½′) on roof, brick in mortar, lime mortar plastering and white washing ..	R.ft.		74	
23(*b*)	Thin mortar bands at ends of roof ..	,,		74	
24	Silicate painting two coats, sooth finish ..	Sqr.		14·09	
25	Teak wood windows frame, 3½″×4½″ glazed shutters with iron fittings, etc., complete, in higher partions of wall	S.ft.		221	
26	Cement concrete flooring 1½″ thick over 3″ jelly concrete in lime mortar and top finished with red colour	Sqr.		14·45	
27	Teak wood finials on roof including fixing and painting	No.		2	
28	Teak wood pendents including fixing and painting	,,		4	
29	Teak wood plain eave board including fixing and painting	R.ft.		160	
30	Teak wood circular ventilator with glazed shutters including fixing and painting ..	S.ft.		14·1	
31	Preparing and fixing sun shades to doors and windows of front and rear halls with teak wood frame and asbestos sheets covering and painting wood works	No.		18	

A. TANDONI RAO,
Executive Engineer.

HASSAN DIVISION.

Notification dated 1st April 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M. on 27th April 1935, for constructing Assistant Superintendent's Quarters at Hassan (Electrical Department). An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing Assistant Superintendent's Quarters at Hassan (Electrical Department)" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing Assistant Superintendent's Quarters at Hassan (Electrical Department) Drawing No. 378.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation in gravelly soil and filling in basement and removing extra earth to a distant place	C.yd.		42	
2(*a*)	Stone jelly concrete in ordinary mortar ..	C.ft.		384	
(*b*)	Size stone in mortar for basement	,,		1,122	
(*c*)	Burnt brick in clay superstructure	,,		1,538	
(*d*)	Do in mortar	,,		460	
(*e*)	Do for arch work	,,		78	
(*f*)	Stone slabs 6″ thick roughly dressed and fixed in mortar	S.ft.		51	
(*g*)	Burnt brick pillars in mortar complete with bond stones as per design $1\frac{1}{8}'$ thick	No.		6	
(*h*)	Cement pointing with thread lining	Sqr.		2.05	
(*i*)	Plastering with lime mortar $\frac{3}{4}''$ thick ..	,,		40.75	
(*j*)	White and colour washing 2 coats	,,		43	
(*k*)	Plain cornice 6″ projection	R.ft.		63	
(*l*)	Chunam border over roof 6″×3″	,,		38	
(*m*)	Binding wall $1\frac{1}{8}'\times\frac{3}{4}'$ brick in mortar and chunam plaster white wash, etc., complete	,,		28	
3	Flooring with I Class Mangalore Tiles on 3″ concrete including cement pointing and thread lining	Sqr.		9	
4 (*a*)	Roofing with I Class Mangalore Tiles on teak wood reepers 2″×1″ complete	Sqr.		15.00	
(*b*)	Ridge tiles set in mortar and cement pointing ..	R.ft.		95	
(*c*)	Teak wood work wrought and put up with 2 coats of wood oiling	C.ft.		88.82	
(*d*)	Plain teak wood eave board 9″×1″ as per drawing	R.ft.		121	
(*e*)	Teak wood finials as per drawing fixed in the roof	No.		2	
(*f*)	Teak wood panelled door complete with all fixtures as per drawing	S.ft.		169	
(*g*)	Teak wood windows with panelled shutters iron bars, etc., complete with fixtures as per drawing	,,		84	
(*h*)	Teak wood glazed ventilators with iron bars, etc., complete with fixtures as per drawing ..	,,		30	
(*i*)	T. W. cup-boards with shelves and without shutters	,,		24	
(*j*)	Painting with chocolate, 2 coats	,,		8.0	
(*k*)	Teak wood plain 1″ thick shelves screwed on T.W. wood pegs 3″×3″ fixed with wall, complete with painting, etc.	,,		38	
5	Constructing sink as per design	Each		1	
6	Fixing wrought iron pipe drains $1\frac{1}{2}''$ in rooms ..	,,		5	
7	Constructing a latrine and silk pattern drains, absorption pits and clearing site, etc. ..	L. S.		..	

Notification dated 1st April 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M., on 27th April 1935, for constructing Line Men's Quarters, one block at Hole-Narsipur and the other at Hassan (including the construction of latrine). An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of.....193 .

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

4. Each tender for each building must be accompanied by a deposit of Rs. 130 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing Line Men's Quarters at Hassan and Hole-Narsipur " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates oft he Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing Line Men's Quarters, one block at Hole-Narasipur and the other at Hassan. G. 381.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earth work excavation ordinary soil and filling in	C.yd.		33	
2 (*a*)	Stone jelly concrete in lime mortar for foundation	C.ft.		287	
(*b*)	Course rubble stone masonry in clay	,,		911	
(*c*)	Burnt brick in clay	,,		1,747	
(*d*)	Burnt brick in lime mortar	,,		347	
(*e*)	Stone slabs 4″ thick roughly dressed and fixed in lime mortar	S.ft.		115	
(*f*)	Binding walls 6″×6″ of brick in lime mortar and chunam plastered, etc., complete	R.ft.		28	
(*g*)	Plastering with lime mortar	Sqr.		43.15	
(*h*)	Pointing with cement mortar	,,		1.45	
(*i*)	White and colour washing, two coats	,,		44.60	
3 (*a*)	Roofing with 1st Class Mangalore Tiles on teak reepers including wood oiling	Sqr.		13.18	
(*b*)	Ridge tiles set in mortar and cement pointed	R.ft.		68	
(*c*)	Ventilating tiles do do	Each		16	
4	Honney wood wrought and put up including wood oiling	C.ft.		50	
5(*a*)	Doors with teak wood frames and Honney wood battened shutters with necessary fittings, etc., complete	S.ft.		78	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
(*b*)	Battened windows with teak frame and Honney woods shutters 1″ thick with iron bars, etc., complete	Sqr.		60	
(*c*)	Chacolate painting, two coats	,,		3.06	
(*d*)	Constructing sinks in bath rooms	Each		4	
6	Providing and fixing mortar and pestle ..	Each		4	
7*	Constructing silk pattern drains leading to absorption pit, etc., complete	L. S.		..	
8	Latrine cest as per details shown separately ..	L. S.		..	

**Note.*—Separate tenders should be given for the quarters at Hassan and Hole-Narsipur.

Abstract estimate for constructing Latrine at Hassan and Hole-Narsipur for Line Men.

G. 257.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earth work excavation and refilling	C.yd.		4	
2 (*a*)	Stone in clay	C.ft.		130	
(*b*)	Burnt brick in mortar	,,		196	
(*c*)	Chunam plastering	Sqr.		4.91	
(*d*)	Cement pointing	,,		0.56	
(*e*)	White washing	,,		5.47	
(8)	Cement plastering ½″ thick	,,		0.79	
(*g*)	Tarring, 2 coats	,,		0.63	
3	Flooring 3″ concrete and cement plastering ½″ thick	,,		0.38	
4	Fixing outlets and constrcting drains	L. S.		..	
5	Providing galvanized iron sheet tubes ..	Each		6	

Note.—Separate tenders should be given for the quarters at Hassan and Hole-Narsipur

---

Notification dated 1st April 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M. on 27th April 1935, for constructing two Inspectors' Quarters, one at Hassan and the other at Hole Narsipur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender for each building must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing Inspectors' Quarters one at Hassan and the other at Hole-Narsipur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing two Inspectors' Quarters—one at Holenarasipur and the other at Hassan.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation in ordinary soil and filling in basement	C.yd.		59	
2 (*a*)	Stone jelly in mortar for foundation ..	C.ft.		442	
(*b*)	Size stone in clay for foundation and basement .	,,		1,383	
(*c*)	Burnt brick in clay for superstructure ..	,,		1,944	
(*d*)	Burnt brick in mortar for do	,,		552	
(*e*)	Stone slabs 6″ thick dressed and fixed ..	S.ft.		171	
(*f*)	Stone slabs 3″ thick and fixed over beam ..	,,		28	
(*g*)	Pointing with cement mortar	Sqr.		2·4	
(*h*)	Plastering with lime mortar	,,		48·22	
(*i*)	White and colour washing	,,		50·62	
(*j*)	Plain cornice 9″	R.ft.		52	
(*k*)	Parapet wall 9″ thick, 1½ ft. high, brick in mortar complete with plastering etc.	R.ft.		50	
3	Flooring with 1″ cement concrete on a bed of 3″ lime concrete complete	Sqr.		8·4	
4 (*a*)	Roofing with I Class Mangalore Tiles on teak reapers with wood oiling	,,		12·03	
(*b*)	Ridge tiles set in mortar with cement pointing .	R.ft.		73	
(*c*)	Madras Terrace complete	Sqr.		2·89	
(*d*)	Matti woodwork with wood oiling	C.ft.		60·0	
(*e*)	Plain teak wood eave board 9″	R.ft.		130	
(*f*)	Doors with teak wood frame and honney wood battened shutters 1″ thick including fixing complete	S.ft.		163	
(*g*)	Window with teak wood frames and Honney wood battened shutters with iron bars, etc.	S.ft.		110	
(*h*)	Teak wood cup-board with honney wood shelves	,,		48	
5	Providing and fixing steel girders (Tata's tested) complete including painting	Cwt.		14·8	
6	Expanded metal 3″×1½″ with ⅛″ stranded with teak wood frame work fixed complete with doorways	S.ft.		111	
7	Chocolate painting 2 coats	Sqr.		11·17	
8	Ventilating tiles (big size)	Each		6	
9	Constructing sinks complete	,,		2	
10	Providing and fixing mortar and pestle ..	,,		1	
11	Chunam border at rear roof	R.ft.		26	
12	Rain water down pipe 3″ diameter fixed ..	,,		50	
13	Providing silk pattern drains, absorption, pit, etc.	L. S.		..	
	Constructing a latrine and drains all round leading to absorption pit, etc.	,,		..	

Notification dated 1st April 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M. *on 27th April* 1935, for constructing four Line Man's Quarters at Hagare, Belur, Hosahally and Madehally. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender for each building must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Line Man's Quarters at (1) Hagare, (2) Belur, (3) Hosahally and (4) Madehally," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing Line Man's Quarters at Hagare, Belur, Hosahally and Madehally. (4 quarters).

O 382.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation and filling in basement ..	C.yd.		40	
2 (*a*)	Stone jelly in mortar	C.ft.		353	
(*b*)	Course rubble stone in clay	,,		1,195	
(*c*)	Burnt brick in clay	,,		2,138	
(*d*)	Do in mortar	,,		433	
(*e*)	Stone slabs 4" thick	S.ft.		144	
(*f*)	Binding walls	R.ft.		28	
(*g*)	Chunam plastering	Sqr.		52·87	
(*h*)	Pointing with cement mortar	,,		1·7	
(*i*)	White and colour washing	,,		54·57	
3 (*a*)	Roofing with 1st Class Mangalore Tiles on teak reepers including wood oiling	Sqr.		16·41	
(*b*)	Ridge tiles set in mortar and cement pointed..	R.ft.		80	
(*c*)	Ventilating tiles do do	Each		20	
4	Honne wood wrought and put up with wood-oiling	C.ft.		53·07	
5 (*a*)	Doors teakwood and honney wood panelled shutters, etc.	S.ft.		98	
(*b*)	Windows do do with iron bars $\frac{3}{4}$" diameter	,,		75	
(*c*)	Chocolate painting	Sqr.		3·84	
6	Constructing sinks	Each		5	
7	Providing and fixing mortar and pestle ..	,,	10-0-0	5	
8	Providing and fixing teakwood finials ..	,,		2	
9	Providing silk drains, absorption pits, etc. ..	L. S.		..	

Note.—Separate tenders should be given for the quarters at Belur, Hagare, Hosahally and Madehally.

Notification dated 2nd April 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 29th April 1935 at 3 P.M. for Restoring Chigahally Thattekere Register No. 625 of Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Chigahally Thattekere Register No. 625 of Hassan Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for restoring Chigahally Thattekere Register No. 625 of Hassan Taluk.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
	Bund.				
1	Earthwork raising the bund with consolidation (including cutting grips)	Cyd.		6,820	
2	Turfing the slopes	S.yd.		9,100	
3	Providing and fixing new grade stones with chiseling figures, painting, etc., complete ..	Each		16	
4	Providing and fixing new Index stones ..	,,		16	
5	Providing and fixing Register No. stone with chiseling figures and painting, etc. ..	,,		1	
6	Providing and fixing B. M. stones new ..	,,		2	
7	Clearing jungle growth on the top and slopes of bund	L.S.			
8	Lead and consolidation charges for using the earth available in excavation of body wall approach and draft clearing	Cyd.		229	
9	Cutting grips for the seat of earth if required extra and other works	L. S.			
	Sluice at R. L. 43·00.				
1	Cutting open bund and refilling with consolidation	C.yd.		71	
2	Earth work excavation	,,		14	
3	Concrete in surki mortar	C.ft.		135	
4	Burnt brick in surki mortar	,,		559	

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
5	Providing and fixing burnt stones slabs 6″ thick in surki mortar with cement pointing ..	S.ft.		82	
5(*a*)	Do do 4½″ thick for bed of cisterns	,,		16	
6	Plastering with surki mortar	Sqr.		3·33	
7	Providing and laying C. I. pipes 6″ diameter (pipes will be supplied departmentally) and jointing them with necessary hemp and cement mortar	R.ft.		36	
8	Drilling holes in orifice slabs	Each		4	
9	Providing and fixing jelly wood plug and iron rods with locking arrangements ..	,,		1	
	Waste Weir.				
1	Earthwork excavation	C.yd.		29	
2	Concrete in surki mortar	C.ft.		303	
3	Burnt brick in surki do	,,		594	
4	Providing and fixing burnt stone slab 6″ thick dressed and fixed with surki mortar and cement pointing	S.ft.		140	
5	Plastering with Surki mortar	..		..	
6	Benching rock for founding the body wall ..	L.S.		..	
7	Clearing approach and draft	C.yd.		200	
8	New rough stone work with jelly packing and wedging	,,		58	

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 22nd March 1935.

The attention of the public is hereby invited to advertisement in pages 670-671, Part VI of the *Mysore Gazette*, dated 28th March 1935, calling for tenders for "Constructing a new Waste weir and protective works to Chordi Jondlukere, Register No. 220 and 296 of Kumsi Sub-Taluk."

Each tender must be accompanied by a Treasury chellan for having deposited a security deposit of Rs. 100 in the first instance and Rs. 100 more is to be credited to Treasury after the tenders are accepted.

The last date for receiving tenders is 2 P.M. on Saturday the 13th April 1935.

B. KRISHNA RAO,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 24th March 1935.

The attention of the public is invited to the advertisement published in pages 671-672 of Part VI of the *Mysore Gazette*, dated 28th March 1935, calling for tenders for the work of constructing Sri Ganapathi Temple at Chikmagalur.

The last date fixed for receipt of tender in this office is 15th April 1935.

L. A. H. WINCKLER,
Executive Engineer.